



+91 9538840277 | mracademyhubli@gmail.com  
+91 9845326115 | www.mrswimmingacademy.com

Regd. Office: #191, Sri Mallikarjuna, Naveen Park, Kusugal Road, Keshwapur, Hubballi - 580 023  
Branches: •Bengaluru •Mysuru •Kalburgi

TO,  
MR. SANJAY J YOGI  
Site Address : MUNDGOD.

09.06.2026

### ELECTRO - MECHANICAL AND WATERPROOFING, POOL TILING WORKS SPECIFICATIONS

|                                                                                                                |                                      |
|----------------------------------------------------------------------------------------------------------------|--------------------------------------|
| <b>SWIMMING POOL SPECIFICATIONS</b>                                                                            | <b>SHAPE OF POOL - DESIGNER POOL</b> |
| (Main Pool -30'X60'X4.5' Kid pool 10'x10'x2.5' within)<br>Plant Room -12'X12'X6'    balancing Tank -12'X12'X6' | <b>TYPE OF POOL - OVERFLOW TYPE</b>  |

|                          |                          |  |
|--------------------------|--------------------------|--|
| <b>MAIN POOL</b>         | <b>MAIN POOL In Feet</b> |  |
| Length                   | 30                       |  |
| Width                    | 60                       |  |
| Depth                    | 4.5                      |  |
| <b>Water Volume Ltrs</b> | <b>20,000</b>            |  |
|                          |                          |  |
| Balancing Tank           | 12'X12'X6'               |  |
| PLANT ROOM               | 12'X12'X6'               |  |

|                                        |                |
|----------------------------------------|----------------|
| <b>Total Pool Volume in Liters</b>     | <b>200000</b>  |
| <b>Total Filtration Volume in Ltrs</b> | <b>200000</b>  |
| <b>Turnover Period</b>                 | <b>4 Hours</b> |
| <b>Filtration Flow rate Required</b>   | <b>50000</b>   |
| <b>Total Tiling Area in Sft</b>        | <b>2730</b>    |
| <b>Total Coping Area in Rft</b>        | <b>396</b>     |
| <b>Total Waterproofing Area in Sft</b> | <b>4062</b>    |

### BILL OF QUANTITY


#### PART-1 - MEP

#### POOL FILTRATION & BASIN EQUIPMENTS / ACCESSORIES - MEP

| SL No. | DESCRIPTION | IMAGE* | WARRANTY** | QTY | UNIT | RATE | AMOUNT |
|--------|-------------|--------|------------|-----|------|------|--------|
|--------|-------------|--------|------------|-----|------|------|--------|

#### A PLANT ROOM EQUIPMENTS

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                                                                                     |                           |     |     |       |             |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|---------------------------|-----|-----|-------|-------------|
| 1 | <b>SWIMMING POOL FILTER :</b><br>Providing supply of Bobbin Wound Sand Filter <b>900 mm Dia</b> fitted with pressure gauge panel, manual air bleeder, UV resistance surface, Non corrosive material, water drain and emptying plug fitted with collector arms and diffuser made from PVC and polypropylene.<br>Design Flow rate : 25 m3/h.<br>Maximum working pressure : 3.5 Bar<br><b>MAKE : Aqvastar- Singapore, HORNER Xpress Aquatix - US,</b> |    | 01 Years for Filter Shell | 1   | Nos | 78700 | 78,700.00   |
| 2 | <b>FILTER MEDIA :</b><br>Supply of Silica sand media for the filtrations bed and testing and commissioning.<br>Sand & Gravel grading : 0.2 - 1.0 mm & 2 - 3mm<br><b>MAKE : RPSP</b>                                                                                                                                                                                                                                                                |    | N/A                       | 450 | Kg  | 25    | 11,250.00   |
| 3 | <b>06 WAY MULTIPORT VALVE 2":</b><br>Supply of 6 way Multiport valve for the filter unit with Pressure guage, connectors & unions etc.<br>Type : Top Mounted.<br><b>MAKE : PENTAIR / MIDAS / AQUATIX / Aqvastar</b>                                                                                                                                                                                                                                |    | 01 Years                  | 1   | Nos | 12500 | 12,500.00   |
| 4 | <b>RECIRCULATING PUMP:</b><br>Supply of <b>3 hp</b> Single phase Self priming low noise pump with built in Pre filter and removable stainer, and unions, Heat and chemical resistant casing with Noryle impeller & diffuser, Mechanical Seal, Class F insulation, IP 55 Protection etc.<br><b>MAKE: HORNER EXPRESS/ AQUATIX / Aqvastar</b>                                                                                                         |    | 01 Years                  | 2   | Nos | 61000 | 1,22,000.00 |
| 5 | <b>POOL MAIN DRAIN:</b><br>Supply of 200mm dia ABS made floor drain with 2" pipe size for the pool water dewatering.<br><b>MAKE: PENTAIR / MIDAS / AQUATIX / Aqvastar</b>                                                                                                                                                                                                                                                                          |  | 02 Years                  | 2   | Nos | 2400  | 4,800.00    |
| 6 | <b>FLOOR INLETS :</b><br>Supply of Wall / Floor inlets to the pool with 2" pipe connection & capable of discharging 5000 - 7000 liter / Hr.<br><b>MAKE : PENTAIR / MIDAS / AQUATIX / Aqvastar</b>                                                                                                                                                                                                                                                  |  | 02 Years                  | 9   | Nos | 1120  | 10,080.00   |

|    |                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                     |          |    |     |        |             |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|----------|----|-----|--------|-------------|
| 7  | <b>WALLCONDUICTS :</b><br>Supply of wall conduits to the pool for Wall inlets & VacuumPoints with 2" pipe connection.<br><b>MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR</b>                                                                                                                                                                                                                            |    | 02 Years | 2  | Nos | 550    | 1,100.00    |
| 8  | <b>VACCUME POINT :</b><br>Supply of Standerd Vaccume Point with treded connection for cleaning the pool.<br><b>MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR</b>                                                                                                                                                                                                                                         |    | 02 Years | 2  | Nos | 900    | 1,800.00    |
| 7  | <b>SWIMMING POOL LADDER:</b><br>Supply of SS 304 Grade imported Swimming Pool ladder with necessary anchoring etc. <b>No of Steps : 04 &amp; 03</b><br><b>MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR</b>                                                                                                                                                                                              |    | 02 Years | 3  | Nos | 22500  | 67,500.00   |
| 8  | <b>OVERFLOW GRATING:</b><br><b>Supply of Standard GRATINGS fitted on the guttur surrounding the Pool</b><br><b>MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR</b>                                                                                                                                                                                                                                         |    | 01 Years | 58 | Rft | 1150   | 66,700.00   |
| 9  | <b>LABOUR CHARGES - PLANT ROOM &amp; BASIN EQUIPMENTS:</b><br>Installation charges for Plant room filtration equipments & pool inside and outside basin fittings etc.                                                                                                                                                                                                                                  |    | 01 Years | 1  | Lsm | 25000  | 25,000.00   |
| 10 | <b>PLUMBING MATERIALS:</b><br>Supply of required Heavy duty 10kg/6kg 1 1/2" PVC/Upvc pipes with required fittings for the Pool and filtration room between plumbing connections etc. All in pasting type.<br>Upvc Pipes - Elbows - Tees - Shoes<br>End Cap - MTA - FTA - Coupling - Upvs Solvent etc<br><b>SCH-40 Upvc pipe or 10 Kgf/cm2 PVC Pipe.</b><br><b>MAKE : ASTRAL, SUPREME, FINOLEX etc.</b> |   | 0        | 1  | Lsm | 145000 | 1,45,000.00 |
| 11 | <b>CONTROL &amp; REGULATING EQUIPMENTS:</b><br>Providing Supply of Imported Ball valves & Nrv to the Pump & filter and Standard ball valves to the Connection Pipe Lines etc.<br><b>MAKE : CEPEX - Spain or Elquelent.</b>                                                                                                                                                                             |  | 01 Years | 18 | Nos | 3800   | 68,400.00   |
| 12 | <b>LABOUR CHARGES - PLUMBING WORKS:</b><br>Laying pipe lines throughout the pool till plant room for inlets, main drains, and vacuum points complete                                                                                                                                                                                                                                                   |  | 01 Years | 1  | Lsm | 25000  | 25,000.00   |

|          |                                                                                                                                                                                                                                                                                  |                                                                                     |          |    |     |       |             |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|----------|----|-----|-------|-------------|
| 13       | <b>UNDERWATER LIGHT:</b><br>Providing & Laying of 24w/18v LED underwater Lights with IP68 ratings                                                                                                                                                                                |    | 02 Years | 14 | nos | 5800  | 81,200.00   |
|          |                                                                                                                                                                                                                                                                                  |                                                                                     |          |    |     |       | 7,21,030.00 |
| <b>B</b> | <b>FILTRATION ROOM ELECTRICAL WORK</b>                                                                                                                                                                                                                                           |                                                                                     |          |    |     |       |             |
| 1        | <b>ELECTRICAL MATERIALS:</b><br>Supply of 1.5 Sqmm x 2 core Electrical cabling with required conduits for Pool pumps to the electrical panels with required clamping etc.                                                                                                        |    | 1 YEAR   | 1  | Lsm | 28000 | 28,000.00   |
| 2        | TRANSFORMER FOR UNDER WATER LIGHTS AC TO DC                                                                                                                                                                                                                                      |                                                                                     | 1 YEAR   | 2  | Nos | 7500  | 15,000.00   |
| 3        | <b>LABOUR CHARGES - POOL ELECTRICAL WORKS:</b><br>Labour charges for Installation of Electrical cabling with required conduits for to Electrical Panel & Pool pumps to the electrical panels with required clamping etc.<br><b>MAKE: V Guard, Finolex, Havells, Polycab Etc.</b> |    | 01 Years | 1  | Lsm | 25000 | 25,000.00   |
|          |                                                                                                                                                                                                                                                                                  |                                                                                     |          |    |     |       | 68,000.00   |
| <b>C</b> | <b>ELECTRICAL CONTROL PANEL WITH TIMER</b>                                                                                                                                                                                                                                       |                                                                                     |          |    |     |       |             |
| 1        | <b>POOL STARTER FOR PUMPS &amp; LIGHTS:</b><br>Supply & fixing of Single Phase starter                                                                                                                                                                                           |   | 01 Years | 2  | Lsm | 4500  | 9,000.00    |
| 2        | <b>TESTING &amp; COMMISSIOINING OF THE POOL:</b><br>After water filling testing, commissioing & running of the pool to ensure the proper running condition of the pool filtration system                                                                                         |  | 0        | 1  | Lsm | 10000 | 10,000.00   |
|          |                                                                                                                                                                                                                                                                                  |                                                                                     |          |    |     |       | 19,000.00   |
| <b>D</b> | <b>SUPPLY OF SWIMMING POOL MAINTENANCE CLEANING KIT</b>                                                                                                                                                                                                                          |                                                                                     |          |    |     |       | -           |
| 1        | <b>VACCU HEAD :</b><br>Supply of Vaccum Head aluminum body with 4 wheels and brush etc.<br><b>MAKE : PENTAIR / AQUATIX.</b>                                                                                                                                                      |  | 0        | 1  | Nos | 4500  | 4,500.00    |

|                            |                                                                                                                                                                                                                                                                                                                            |                                                                                     |                        |      |     |       |                    |
|----------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|------------------------|------|-----|-------|--------------------|
| 2                          | <b>VACCUM HOSE:</b><br>Supply of Vacuum Hose <b>15 Meter</b> Length for the Pool Cleaning.<br><b>MAKE : PENTAIR / AQUATIX.</b>                                                                                                                                                                                             |    | 0                      | 1    | Nos | 5500  | 5,500.00           |
| 3                          | <b>TELESCOPIC ROD:</b><br>Supply of Telescopic rod 9-27' length aluminium pole expandable type.<br><b>MAKE : PENTAIR / AQUATIX.</b>                                                                                                                                                                                        |    | 0                      | 1    | Nos | 5800  | 5,800.00           |
| 4                          | <b>DEEP LEAF RAKE:</b><br>Supply of Deep net for the pool cleaning.<br><b>MAKE : PENTAIR / AQUATIX.</b>                                                                                                                                                                                                                    |    | 0                      | 1    | Nos | 1400  | 1,400.00           |
| 5                          | <b>WATER TEST KIT:</b><br>Supply of Pool water Test Kit for pH and Chlorin.<br><b>MAKE : PENTAIR / AQUATIX.</b>                                                                                                                                                                                                            |    | 0                      | 1    | Nos | 700   | 700.00             |
| 6                          | <b>POOL BRUSH:</b><br>Supply of Pool cleaning Brush with aluminium back.<br><b>MAKE : PENATIR / AQUATIX.</b>                                                                                                                                                                                                               |    | 0                      | 1    | Nos | 1400  | 1,400.00           |
| 7                          | <b>POOL CHEMICALS :</b><br>Initial Supply of Pool Chemiclas like Tcca 90, Algecide, Ph Balancing Chemiclas etc for initial Pool cleaning etc.                                                                                                                                                                              |                                                                                     | 0                      | 1    | Lsm | 10000 | 10,000.00          |
|                            |                                                                                                                                                                                                                                                                                                                            |                                                                                     |                        |      |     |       | 29,300.00          |
|                            |                                                                                                                                                                                                                                                                                                                            |                                                                                     | <b>TOTAL (A+B+C+D)</b> |      |     |       | <b>8,37,330.00</b> |
| <b>Part2:POOL FINISHES</b> |                                                                                                                                                                                                                                                                                                                            |                                                                                     |                        |      |     |       |                    |
| 1                          | <b>WATER PROOFING :</b><br>Supply and applying of <b>ELESTO-MERICO</b> Two coat wheather proof high flexibility cementisious mortar with crack bridging capacity up to 2mm, Edge band for all the corners for swimming pools,Balancing Tank, Filtration room & overflow Gutter.<br><b>MAKE : NIPPON/MAPEI/KERAKOLL/MYK</b> |   | 05 Years               | 4062 | Lsm | 55    | 2,23,410.00        |
| 2                          | <b>COPING STONE: LABOR CHARGES ONLY(**Excluding Granite/cement)</b><br>Labor charges for fixing of 20mm thick Granite stone as coping stone and noosing etc.<br><b>MAKE: SADARAHALLI / BANGALORE STONE.</b>                                                                                                                |  | 1 year                 | 396  | Sft | 80    | 31,680.00          |
| 3                          | <b>SWIMMING POOL TILES :</b><br>Supply of RECTIFIED 12X12 INCHES tiles standard colour for the floor and walls of the pool.                                                                                                                                                                                                |  | 1 year                 | 2730 | Sft | 90    | 2,45,700.00        |

| 4 | Labour charges for Tiles fixing & Grouting with required Tools and materials for cleaning after Grouting etc. | RPSP | 01 Year for Tiles Fixing | 2730        | Sft | 90 | 2,45,700.00  |
|---|---------------------------------------------------------------------------------------------------------------|------|--------------------------|-------------|-----|----|--------------|
| 5 | Transportation and miscellenious charges                                                                      |      |                          |             |     |    | 50,000.00    |
|   |                                                                                                               |      | TOTAL                    |             |     |    | 7,96,490.00  |
|   |                                                                                                               |      |                          |             |     |    |              |
|   | DESCRIPTION                                                                                                   | QTY  | UNIT                     | AMOUNT      |     |    |              |
| 1 | Cost for Pool Electromechanical works                                                                         | 1    | Set                      | 8,37,330.00 |     |    |              |
| 2 | Cost for Waterproofing,Granite Copping & Swimming Pool Tiles work                                             | 1    | Set                      | 7,96,490.00 |     |    |              |
|   |                                                                                                               |      | <b>*TOTAL Rs.</b>        |             |     |    | 16,33,820.00 |

[\\*GST@18% EXTRA](#)

**Terms and Conditions:**

1. Single phase connection up to the plant room is in your scope of work.
2. Back wash line after the plant room and water supply to balance tank is in your scope.
3. All Civil works are at your scope.

**Payment Terms:**

1. 30% Payment along with the PO,
2. 30% payment after bar bending,
3. 30% During tile fixing work,
4. 10% On successful commissioning and testing.

Thanking you,  
**For M R SWIMMING POOL & SPA CONSTRUCTION COMPANY**

**(Rajesh V Shetti)**  
**9538840277/9845326115**

