



+91 9538840277
+91 9845326115

mracademyhubli@gmail.com
www.mrswimmingacademy.com

Regd. Office: #191, Sri Mallikarjuna, Naveen Park, Kusugal Road, Keshwapur, Hubballi - 580 023
Branches: •Bengaluru •Mysuru •Kalburgi

TO,

Client Name : MR. NAVEEN PEEROJI

Site Address : TADAS.

08.05.2026

ELECTRO - MECHANICAL AND WATERPROOFING, POOL TILING WORKS SPECIFICATIONS

SWIMMING POOL SPECIFICATIONS		SHAPE OF POOL - RECTANGLE POOL
(Main Pool 30'X20'X4.5')	Plant Room -8'X8'X6'	TYPE OF POOL - SKIMMER TYPE

MAIN POOL	In FT
Length	30
Width	20
Depth	5
Water Volume	74000

PLANT ROOM SIZE	8'X8'X6'
-----------------	----------

Total Pool Volume in Liters	74000
Total Filtration Volume in Ltrs	74000
Turnover Period	4 Hours
Total Tiling Area in Sft	1100
Total Coping Area in Rft	104
Total Waterproofing Area in Sft	1420

BILL OF QUANTITY

PART-1 - MEP

POOL FILTRATION & BASIN EQUIPMENTS / ACCESSORIES - MEP


SL No.	DESCRIPTION	IMAGE*	WARRANTY**	QTY	UNIT	RATE	AMOUNT
--------	-------------	--------	------------	-----	------	------	--------

A PLANT ROOM EQUIPMENTS

1	SWIMMING POOL FILTER : Providing supply of Bobbin Wound Sand Filter 700 mm Dia fitted with pressure gauge panel, manual air bleeder, UV resistance surface, Non corrosive material, water drain and emptying plug fitted with collector arms and diffuser made from PVC and polypropylene. MAKE : AQVASTAR- Singapore, HORNER Xpress Aquatix - US,		01 Years for Filter Shell	1	Nos	48372	48,372.00
2	FILTER MEDIA : Supply of Silica sand media for the filtrations bed and testing and commissioning. Sand & Gravel grading : 0.2 - 1.0 mm & 2 - 3mm MAKE : RPSP		N/A	250	Kg	25	6,250.00
3	06 WAY MULTIPORT VALVE 1.5": Supply of 6 way Multiport valve for the filter unit with Pressure guage, connectors & unions etc. Type : Top Mounted. MAKE : AQVASTAR- Singapore, HORNER Xpress Aquatix - US,		01 Years	1	Nos	12400	12,400.00
4	RECIRCULATING PUMP: Supply of 1 hp Three phase Self priming low noise pump with built in Pre filter and removable stainer, and unions, Heat and chemical resistant casing with Noryle impeller & diffuser, Mechanical Seal, Class F insulation, IP 55 Protection etc. MAKE : AQVASTAR- Singapore, HORNER Xpress Aquatix - US,		01 Years	2	Nos	35145	70,290.00
5	POOL MAIN DRAIN: Supply of 200mm dia ABS made floor drain with 2" pipe size for the pool water dewatering. MAKE: PENTAIR / MIDAS / AQUATIX / AQVASTAR		02 Years	2	Nos	1900	3,800.00
6	WALL INLETS : Supply of Wall / Floor inlets to the pool with 2" pipe connection & capable of discharging 5000 - 7000 liter / Hr. MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR		02 Years	6	Nos	920	5,520.00

7	SWIMMING POOL LADDER: Supply of SS 304 Grade imported Swimming Pool ladder with necessary anchoring etc. No of Steps : 03 &04 MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR		02 Years	2	Nos	22500	45,000.00
8	STD SKIMMER: Supply of Standard SKIMMER fitted on the WALL of the Pool MAKE : PENTAIR / MIDAS / AQUATIX / AQVASTAR		01 Years	2	Nos	6500	13,000.00
9	LABOUR CHARGES - PLANT ROOM & BASIN EQUIPMENTS: Installation charges for Plant room filtration equipments & pool inside and outside basin fittings etc.		01 Years	1	Lsm	25000	25,000.00
10	PLUMBING MATERIALS: Supply of required Heavy duty 10kg/6kg 1 1/2" PVC/Upvc pipes with required fittings for the Pool and filtration room between plumbing connections etc. All in pasting type. Upvc Pipes - Elbows - Tees - Shoes End Cap - MTA - FTA - Coupling - Upvs Solvent etc SCH-40 Upvc pipe or 10 Kgf/cm2 PVC Pipe. MAKE : ASTRAL, SUPREME, FINOLEX etc.		0	1	Lsm	115000	1,15,000.00
11	CONTROL & REGULATING EQUIPMENTS: Providing Supply of Imported Ball valves & Nrv to the Pump & filter and Standard ball valves to the Connection Pipe Lines etc. MAKE : CEPEX - Spain or Equelelnt.		01 Years	18	Nos	3800	68,400.00
12	LABOUR CHARGES - PLUMBING WORKS: Installation charges for Plant room filtration equipments & pool inside and outside basin fittings etc. MAKE:		01 Years	1	Lsm	25000	25,000.00
13	UNDERWATER LIGHT: Providing & Laying of 24w/18v LED underwater Lights with IP68 ratings		02 Years	6	nos	5800	34,800.00
							4,72,832.00
B	FILTRATION ROOM ELECTRICAL WORK						

1	ELECTRICAL MATERIALS: Supply of 1.5 Sqmm x 2 core Electrical cabling with required conduits for Pool pumps to the electrical panels with required clamping etc. MAKE: V Guard, Finolex, Havells, Polycab Etc.		0	1	Lsm	15000	15,000.00
2	LABOUR CHARGES - POOL ELECTRICAL WORKS: Labour charges for Installation of Electrical cabling with required conduits for to Electrical Panel & Pool pumps to the electrical panels with required clamping etc. MAKE: V Guard, Finolex, Havells, Polycab Etc.		01 Years	1	Lsm	20000	20,000.00
							35,000.00
C	ELECTRICAL CONTROL PANEL WITH TIMER						
1	POOL STARTER FOR PUMPS & LIGHTS: Supply & fixing of Single Phase starter		01 Years	2	Lsm	3800	7,600.00
2	TRANSFORMER FOR POOL LIGHTS: AC TO DC CONVERTING 12V TRANSFORMER		01 YEARS	1	Nos	7500	7,500.00
3	TESTING & COMMISSIOING OF THE POOL: After water filling testing, commissioing & running of the pool with required manpower and chemicals for a month time to ensure the proper running condition of the pool filtration system and the pool water clean & Neat. MAKE: RPSP		0	1	Lsm	10000	10,000.00
							25,100.00
D	SUPPLY OF SWIMMING POOL MAINTENANCE CLEANING KIT						-
1	VACCUM HEAD : Supply of Vaccum Head ABS body with 4 wheels and brush etc. MAKE : PENTAIR / AQUATIX.		0	1	Nos	2800	2,800.00
2	VACCUM HOSE: Supply of Vaccum Hose 9 Meter Length for the Pool Cleaning. MAKE : PENTAIR / AQUATIX.		0	1	Nos	3500	3,500.00

3	TELESCOPIC ROD: Supply of Telescopic rod 9m length aluminium pole expandable type. MAKE : PENTAIR / AQUATIX.		0	1	Nos	4200	4,200.00
4	DEEP LEAF RAKE: Supply of Deep net for the pool cleaning. MAKE : PENTAIR / AQUATIX.		0	1	Nos	1400	1,400.00
5	WATER TEST KIT: Supply of Pool water Test Kit for pH and Chlorin. MAKE : PENTAIR / AQUATIX.		0	1	Nos	700	700.00
6	POOL BRUSH: Supply of Pool cleaning Brush with aluminium back. MAKE : PENATIR / AQUATIX.		0	1	Nos	1400	1,400.00
7	POOL CHEMICALS : Supply of Pool Chemiclas like Tcca 90, Algecide, Ph Balancing Chemiclas etc for initial Pool cleaning etc.		0	1	Lsm	5000	5,000.00
							19,000.00
			TOTAL (A+B+C+D)				5,51,932.00
Part2:POOL FINISHES							
1	WATER PROOFING : Supply and applying of ELESTO-MERICO Two coat wheather proof high flexibility cementisious mortar with crack bridging capacity up to 2mm, Edge band for all the corners & Brush bond of 2 coats for swimming pools,Balancing Tank, Filtration room & overflow Gutter. MAKE : NIPPON/MAPEI/KERAKOLL/NIPPON		05 Years	1420	Lsm	65	92,300.00
2	COPING STONE: LABOR CHARGES ONLY(**Excluding Granite/cement) Labor charges for fixing of 20mm thick Granite stone as coping stone with required sand, cement or Adhesive including transsporation and unloading charges etc. MAKE: SADARAHALLI / BANGALORE STONE.		0	104	Sft	80	8,320.00
3	SWIMMING POOL TILES : Supply of 20mm x 20mm size Glass Mosaic tiles standard colour for the floor and walls of the pool. MAKE:		0	1100	Sft	90	99,000.00
4	Labour charges for Tiles fixing & Epoxy Grouting with required Tools and materials for cleaning after Grouting etc.	RPSP	01 Year for Tiles Fixing	1100	Sft	110	1,21,000.00
			TOTAL				3,20,620.00

	DESCRIPTION	QTY	UNIT	AMOUNT
1	Cost for Pool Electromechanical works	1	Set	5,51,932.00
2	Cost for Waterproofing, Granite Copping & Swimming Pool Tiles work	1	Set	3,20,620.00
			*TOTAL Rs.	8,72,552.00

[*GST@18% EXTRA](#)

Terms and Conditions:

1. Single phase connection up to the plant room is in your scope of work.
2. Back wash line after the plant room and water supply to balance tank is in your scope.
3. All Civil works mentioned above are at our scope.

Payment Terms:

1. 30% Payment along with the PO,
2. 30% payment after bar bending,
3. 30% During tile fixing work,
4. 10% On successful commissioning and testing.

Thanking you,

For M R SWIMMING POOL & SPA CONSTRUCTION COMPANY

(Rajesh V Shetti)
9538840277/9845326115

